



## **ARMY PUBLIC SCHOOL**

**NEAR HANUMAN CAMP, SHAHIBAUGH, AHMEDABAD CANTT**


### **CALL FOR TENDER**

Sealed tender is hereby invited for Construction of Mini Football Court as per details mentioned in tender document. Tender document is available for issue in the school office on all working days with effect from 28 Dec 2023 to 03 Jan 2024 between 0900 hrs to 1400 hrs on cash payment of Rs 500/- only. The tender document available on school website [apsahmedabad.co.in](http://apsahmedabad.co.in). The document dully filled in all respect alongwith DD of 500/- in favour of **Army Public School Ahmedabad** (if Downloaded from website [apsahmedabad.co.in](http://apsahmedabad.co.in)) to be delivered in the School Quotation box placed at Main Gate in a sealed envelope addressed to the **Principal, Army Public School Ahmedabad** latest by 03 Jan 2024 (1100 hrs). For any query 9427440717

Principal

Army Public School, Ahmedabad Cantt






**TENDER DOCUMENTS**  
**ARMY PUBLIC SCHOOL AHMEDABAD CANTT**  
**(Price Rs 500/-)**

**TENDER FOR CONSTRUCTION OF MINI FOOTBALL COURT**

1.Total Cost (Including of all taxes) on the following branded items:-

Ser No	Nomenclature	Unit	Cost per unit	Total Cost
	<b>MINI FOOTBALL COURT - 25 M X 17 M</b>			
	<b>EXCAVATION &amp; RCC WORK</b>			
1	Surface Preparation:- Trimming, surface dressing, Filling, compaction and leveling of earth/Soil not exceeding 100 mm for laying of successive layer of carpet lawn as per instructions of Engineer - in- charge. Above 100mm undulation under client scope.	430 SQM		
2	Providing and poring in position CC work in site mix cement concrete designed for M10 strength with 1:3:6 ratio of cement sand and aggregates leaving dowels if required as per required size and shape, provision of cutouts in slabs if any, with consolidating with mechanical vibrators, curing by forming ponds or otherwise nemboosing casting date, hacking the exposed surface to receive plaster if needed, etc. complete.	56 M3		
3	Providing, laying and fixing in position (Thermo mechanically Treated Reinforcement (TMT and / or High yield strength Deformed (Tor steel) bars of all grades) steel reinforcement in all reinforced concrete work, including straightening, cutting, removal of loose rust by wire brush and coating with cement slurry, bending, hoisting, laying in position to the shape and profile required at all levels and heights as per Drawing and design and/ or as directed, binding with 18 gauge MS annealed wire etc. complete.	1250KG		
4	LDPE Polymer Sheet:- Providing & Laying in position LD Polymer Sheets of 200 Micron thickness as Vapour barrier on top of compacted subgrade of WMM or above PCC bed and below concrete floor to allow for Shrinkage, creep movement of floor as per drawings and as per instructions of the Engineer in charge etc. complete	430 SQM		
5	Providing and poring in position CC work in site mix cement concrete designed for M25 strength with 1:1:2 ratio of cement sand and aggregates leaving dowels if required as per required size and shape, provision of cutouts in slabs if any, with consolidating with mechanical vibrators, curing by forming ponds or otherwise nemboosing casting date, hacking the exposed surface to receive plaster if needed, etc. complete.	56 M3		
6	Providing and constructing burnt brick masonry at all levels in cement mortar 1:6 for walls, steps, etc. with best quality locally available bricks in 1st class English bond including transoms and mullions as per instructions, necessary scaffolding, raking out joints, curing, etc. complete.	20 CUM		






7	External sand faced cement plaster minimum 20 MM thick at all levels to the external surfaces of RCC & Masonry work or where directed in 2 coats, 1st coat of 12 MM thick in 1:4 proportion and 2nd coat of 8 MM thick in 1:3 proportion with waterproofing additive of Pidilite/ Fosroc/ Sunanda / Roff or equivalent make and Nina fibers including providing and RCC beams or columns before plastering, grooves, bands, drip moulds etc. scaffolding, curing, scraping surface for key for 2nd coat etc. complete. (Only washed and screen river sand to be used)	150 SQM		
8	Providing and laying of fine yellow river sand in 150mm thickness, evenly laid on well compacted and prepared base as per the levels and other details shown in the drawings as per the instructions of Engineering -In-Charge complete.	55 CUM		
9	Excavation for the demarcated area and for the foundations of columns footings, walls, steps, ramps, etc. as per the drawings and instructions up to a depth of 300MM. including recording levels, shoring, strutting, refilling & compacting around walls, and footings,.	15 CUM		
10	Carting material from the site Dispose off the material out of the premises as suggested by engineer/incharge on the site	15 CUM		
11	Providing and laying 60" x 10" size granite stone with 15MM thickness in 1:4 Cement/sand mortar including all material and fixing labour	25 SQM		
12	Prov. & applying asianpaint apex paint in desired shade/colour with proper surface preparation like removing all dust and loose particles, scratching old paint, priming, crack filling and two coat apex paint with all safety protocols for all height and levels.	125 SQM		
13	Prov. & installing stadium Lights of 125 Watt with two years warranty	4 NOS		
<b>TOTAL:</b>				

2. Rates quoted should be inclusive all charges i.e. accessories, transportation, fixing, etc complete. L1 vendor will be decided on total cost of the items. No additional payment will be made.
3. Quoted rates must be valid upto six months from the date of submission of tender.
4. Vendors are advised to conduct site survey before submission of quotation.
5. Service/Pickup Center should be "Ahmedabad City".
6. TDS on total cost will be deducted as per Govt policy.
7. All tender documents will be signed by the authorized firm's representative and firm's rubber stamp will be affixed on all the pages of the documents including envelope in which the tender document will be sealed.
8. Tender for requisite job/items will clearly be mentioned on top of the envelope.






9. Photocopy of Adhar Card, GST Registration, PAN card Photo of shop and will also be attached with the tender document.
10. The firm must be registered and should be authorized dealer of the consigned items.
11. If the requisite items/job will not be supplied/done in the prescribed period, appropriate penalty to be decided by the Management, which the vendor have to be paid.
12. Firm to be ensures standard quality of material to be supplied/ installed.
13. Payment will be made after supply of the items/completion of work and checking suitability and serviceability by the board of office.
14. Firms to mention their full address with contact number on the envelope.
15. Time period for supply completion - 21 days
16. Last date of submission of tender - 1100 Hrs **03 Jan 2024**
17. Date of Opening of tenders - **03 Jan 2024(1115 Hrs)**. If the tender will not be opened on 17 Nov 2023 due to any exigencies, same will be intimated to the firms telephonically.

  
Principal

Army Public School, Ahmedabad Cantt  
Principal  
Army Public School  
Ahmedabad Cantt





**To be filled by the Firm before Delivery**

Name & Address of the firm : \_\_\_\_\_

TIN No (Compulsory) : \_\_\_\_\_

GST No (Compulsory) : \_\_\_\_\_

Name of the Firm's Owner/Representative : \_\_\_\_\_

Signature of the firm's owner with seal : \_\_\_\_\_

Telephone / Mobile No : \_\_\_\_\_

E-mail address : \_\_\_\_\_

Date of Depositing of the Tender : \_\_\_\_\_